



Appendix B:

Culvert Inventory

| Milepost | Diameter (in) | Arch Diameter (in) | Dimensions (in) | Length (ft) | Type | Condition | Environmental | Comments |
|----------|---------------|--------------------|-----------------|-------------|---------------------|-----------|---------------|---|
| 0.11 | | 96x69 | | 68 | CMPA | Good | No | |
| 0.31 | 30 | | | 100 | RCP | Poor | Yes | |
| 1.70 | 24 | | | 58 | RCP | Good | No | |
| 1.94 | 24 | | | 52 | RCP | Good | No | |
| 2.15 | 24 | | | 68 | RCP | Good | No | |
| 2.53 | 24 | | | 60 | RCP | Good | No | |
| 2.96 | 24 | | | 68 | RCP | Good | No | |
| 3.11 | | 60x48 | | 110 | CMPA | Fair | Yes | |
| 3.13 | 24 | | | 102 | CMP | Good | No | |
| 3.16 | | | 72x48 | 56 | Concrete Stock Pass | Fair | No | |
| 3.23 | 24 | | | 64 | RCP | Poor | Possible | |
| 3.32 | | 50x26 | | 68 | CMPA | Fair | No | |
| 3.34 | 36 | | | 90 | RCP | Fair | Yes | |
| 3.52 | 24 | | | 82 | RCP | Poor | Yes | Roots growing in culvert |
| 3.84 | 24 | | | 60 | RCP | Fair | No | |
| 3.94 | 24 | | | 60 | RCP | Fair | No | |
| 4.07 | 24 | | | 70 | RCP | Good | No | |
| 4.24 | | | 72x48 | 62 | Concrete Stock Pass | Good | No | |
| 4.38 | 24 | | | 54 | RCP | Fair | No | |
| 4.52 | 24 | | | 56 | RCP | Good | No | |
| 4.72 | 24 | | | 70 | RCP | Good | No | |
| 5.15 | 24 | | | 62 | RCP | Fair | No | |
| 5.41 | 24 | | | 58 | CMP | Poor | No | Up stream crushed |
| 5.69 | 24 | | | 56 | RCP | Good | No | |
| 5.87 | 24 | | | 62 | RCP | Fair | No | |
| 5.98 | | | 72x48 | 50 | Concrete Stock Pass | Fair | Yes | Partially Filled |
| 6.29 | 18 | | | 50 | CMP | Poor | No | Plugged |
| 6.59 | 24 | | | 76 | RCP | Good | No | |
| 6.79 | 24 | | | 56 | RCP | Good | No | |
| 7.07 | 24 | | | 60 | RCP | Good | No | |
| 7.62 | 84 | | | 60 | CMP | Good | Yes | |
| 7.91 | 48 | | | 60 | RCP | Fair | Yes | |
| 8.07 | 24 | | | 54 | RCP | Good | Yes | |
| 8.49 | 18 | | | 126 | CMP | Poor | Yes | Abandoned |
| 8.51 | 60 | | | 58 | CMP | Good | Yes | |
| 9.09 | 36 | | | 64 | RCP | Fair | Yes | |
| 9.69 | 24 | | | 56 | RCP | Poor | Yes | Fully submerged |
| 10.27 | 24 | | | 58 | RCP | Fair | Yes | |
| 10.39 | | 60x36 | | 70 | CMPA | Poor | Yes | |
| 11.53 | | 35x24 | | 56 | CMPA | Good | No | |
| 11.72 | 24 | | | 70 | RCP | Good | Yes | |
| 11.74 | 48 | | | 84 | CMP | Good | Yes | |
| 12.18 | 24 | | | 60 | RCP | Poor | Yes | Downstream segment detached |
| 12.84 | 24 | | | 58 | RCP | Fair | Yes | |
| 13.99 | 48 | | | 50 | RCP | Poor | Yes | Upstream and downstream side first segment unattached |
| 14.03 | 36 | | | 84 | RCP | Poor | Yes | Upstream side 2 segments unattached |
| 14.11 | | | | | CMP | Good | No | Siphon crosses roadway |
| 14.15 | | | | | CMP | Good | No | Siphon crosses ROW |
| 14.18 | | | | | CMP | Good | No | Siphon crosses ROW |
| 14.25 | 18 | | | 48 | CMP | Good | No | |
| 14.26 | 18 | | | 56 | CMP | Good | Possible | |
| 14.28 | 24 | | | 52 | CMP | Fair | Yes | Culvert half full |
| 14.64 | 24 | | | 46 | CMP | Good | Possible | |

| Milepost | Diameter (in) | Arch Diameter (in) | Dimensions (in) | Length (ft) | Type | Condition | Environmental | Comments |
|----------|---------------|--------------------|-----------------|-------------|------|-----------|---------------|-----------|
| 15.36 | 24 | | | 40 | CMP | Good | Yes | |
| 15.89 | 24 | | | 46 | CMP | Good | Yes | |
| 16.07 | 24 | | | 72 | CMP | Good | No | |
| 16.33 | 18 | | | 42 | CMP | Good | Yes | |
| 16.39 | 18 | | | 48 | CMP | Good | No | |
| 16.62 | 18 | | | 42 | CMP | Good | Yes | |
| 16.74 | | | 144x96 | 32 | RCB | Good | No | |
| 16.91 | 18 | | | 52 | CMP | Good | No | |
| 17.14 | 18 | | | 66 | CMP | Good | No | |
| 17.43 | 30 | | | | CMP | | | Abandoned |
| 17.49 | | | 144x72 | 40 | RCB | Good | Yes | |
| 17.71 | 18 | | | 38 | CMP | Good | No | |
| 17.85 | 18 | | | 46 | CMP | Good | No | |
| 18.10 | | | 96x36 | 68 | RCB | Good | Yes | |
| 18.75 | 18 | | | 38 | CMP | Good | No | |
| 19.26 | 18 | | | 40 | CMP | Good | No | |
| 19.44 | 18 | | | 46 | CMP | Good | No | |